

1 120056

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,186 ~~0000~~
OF C NW, SEC. 4, T 30 S, R 18 W/E

2080 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Parkin "C" Well # 1

Operator: Vincent Oil Corporation

County Kiowa

Name & Address 125 North Market, Suite 1110

Well Total Depth 5070 Mississippi 164.78 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 519

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 9:00 pm Day: 26 Month: October Year: 1985

Plugging proposal received from Norman Hogan

(company name) Wheatatate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1147' Elevation N/A

1st plug at the base of the Anhydrite (1050) with 50 sx cement

2nd plug 50' out of the surface pipe (550) with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:45 pm Day: 26 Month: October Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1160' with 50 sx cement, 2nd plug at 545' with 50
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to
circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE NOV 4 1985

NOV 1 1985

Signed Don C. Ubel (TECHNICIAN)

INV. NO. 10895

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84