

1 040871

7-22

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,937-0001

C SW SW, SEC. 4, T 30 S, R 18 W X

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31289

Lease Name Schmidt "B" Well # 1-4

Operator: NJRE Operating Company

County Kiowa

Name & Address 2400 Bank IV Ctr.

Well Total Depth 5000 162.50 feet

15 W. 6th St.

Conductor Pipe: Size \_\_\_\_\_ feet

Tulsa, OK 74119

Surface Casing: Size 8 5/8 feet 528

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:45 p.m. Day: 22 Month: 7 Year: 19 94

Plugging proposal received from Bob Carpenter

(company name) NJRE Operating Co. (phone) 918-652-7908

logs: 4 1/2" at 5000' w/150 sx cement, PBTD 4825', Perfs at 4857-60, 4762-67'

1st plug sand back to 4710' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 22 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4710' and dumped 4 sx cement on top of

sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 400 psi.

7-28-94

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1300' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)  
observe this plugging.

INVOICED

DATE 7-28-94

INV. NO. 40920

Signed [Signature]

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
FORM C  
Rev.