

6 061484

5-10-88

436

API NUMBER 15-009.19485.0000

NE, SEC. 13, T20 S, R 11 (W/B)

2970 feet from S section line
330 feet from E section line

Lease Name Peters Well # 1

County Barton 106.54

Well Total Depth 3278 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 105

Abandoned Oil Well x Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:30 AM Day: 10 Month: May Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2457

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:00 AM Day: 10 Month: May Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 105' w/cwc. 5 1/2" set at 3277' /

Top perf at 3275'. Plugged bottom w/sand and 5 sks cement to 3225'.

Pipe parted and recovered 489'. Pumped in 8 5/8".

25 sks cement followed w/ 5 sks Hulls in 100 sks cement w/400 Psi.

RECEIVED

STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-27-88

INV. NO. 21051

Conservation Division Wichita, Kansas

Signed Gilbert G. Scheck (TECHNICIAN)

Gilbert G. Scheck

FORM CP-2/3 Rev. 01-84

LR