

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23154-00-00
Spot: CSWNENW Sec/Twnshp/Rge: 13-20S-11W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: BARBER Well Number: 1
County: BARTON Total Vertical Depth: 3263 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Production Casing Size: 5.5 feet: 3261 140 SX CMT
Surface Casing Size: 8.625 feet: 301 250 SX CMT

\$106.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2003 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 190 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/24/2003 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3180' and topped with 5 sxs cement.
Cut off casing at 2408'.
Pulled up to 1300' - mixed and pumped 90 sxs cement with 300# hulls.
Pulled up to 460' - spotted 30 sxs cement with 100# hulls.
Pulled up to 230' - circulated cement with 60 sxs.
POOH. Topped with 10 sxs cement.

RECEIVED
MAY 01 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-2-03

IN NO 2003061484

APR 28 2003

PARRISH CORPORATION
110 N. MARKET, #201
WICHITA, KS 67202

#1 BARBER


13-20-11W
SW NE NW

CONTR H-30 DRILLING, INC.

CTY BARTON

GEOLOGICAL

FIELD CHASE-SILICA



ELV 1754 KB SPD 7/6/83

CARD
ISSUED 9/1/83

IP P 45 BOPD, NW

API 15-009-23,154

ARB OH 3261-3263

SMP	Tops	Depth/Datum
ANH		459+1295
B/ ANH		472+1282
TOP		2594- 840
HEEB		2859-1105
BR LM		2979-1225
LANS		3000-1246
ARB		3260-1506
RTD		3263-1509

8 5/8 " 301 / 250SX; 5 1/2 " 3261 / 140SX

DST (1) 3010-70 (LANS B,C) / 30-45-60-60, 160' GIP, REC 125'
VSO & GCM, SIP 492-361#, FP 29-39 / 39-49#, BHT 100°

DST (2) 3155-3200 (LANS J&K) / 30-30-30-30, REC 20' GCM,
SIP 68-68#, FP 39-39 / 39-39#, BHT 108°

DST (3) 3247-63 (ARB) / 30-60-30-60, REC 1740' GL GSY OIL,
SIP 719-719#, FP 167-462 / 511-610#, BHT 108°

MICR - CO (ARB OH 3261-3263), SWB LO, FU 2150' GL OIL / 13
HRS, T&R, POP, P 45 BOPD, NW, 8/17/83

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS