

4-061163

6-29

~~069-07238~~

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 05-30-50
NW NE NE /4 SEC. 13, 20 S, 11 W
4950 feet from S section line
990 feet from E section line

Operator license# 31086
Operator: Richland Drilling
Address: 598 2nd Avenue
Beaver, Kansas 67517

Lease: Peters Well # 8
County: Barton
Well total depth 3272 ^{106.34} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 161 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 11:00 A.M. Day: 29 Month: June Year: 1998

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 180 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.
Dakota 0'-200'. Anhydrite 456'-469'. Salt Section 956'-1246'.

STATE CORPORATION COMMISSION
RECEIVED

JUL 10 1998

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

WICHITA, KANSAS

Completed: Hour 2:00 P.M., Day: 29, Month: June, Year: 1998

Actual plugging report: 8 5/8" set to 161' w/75 sxs. 5 1/2" to 3270' w/75 sxs.
O.H. 3270' - 3272'. Hit solid bridge at 1400'+ and pounded on with bailer. Spotted 5 sxs
cement with dump bailer on top of bridge. Shot casing loose at 1400' and pulled to 1300'.
Mixed and pumped 90 sxs cement with 300# hulls. Pulled casing to 500' and pumped 40 sxs
cement with 100# hulls. Pulled casing to 150' and circulated cement with 30 sxs. Pulled
casing and topped with 20 sxs cement.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD
Bottom plug(in place): YES , CALC , NO
Plugged through TUBING , CASING .
Anhy.plug: YES NO
Dakota plug: YES NO
Elevation: 1751 GL

I did[] / did not[] observe the plugging.

[Signature]
(agent)

INVOICED

DATE JUL 13 1998

INV. NO. 50907