

15.009.14569.0000

To: 6 061287
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 40,197-C C-2516
SW, SEC. 16, T 20 S, R 11 W/E
1320 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5025

Operator: Tomlinson Oil Co.
Name & Address: Box 1588
Great Bend, Kansas 67530

Lease Name Scheufler Well # 3 - SWD
County Barton 127.40
Well Total Depth 3920 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 288'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service License Number _____

Address Ness City, Ks.

Company to plug at: Hour: 8:00 AM Day: 21 Month: July Year: 19 87

Plugging proposal received from Joe Casper

(company name) Tomlinson Oil Co. (phone) 316-792-1361

were: Order 25 sks Common Cement, 400 sks 65/35 Pozmix, 10% Gel, 2%
Econolite and 10 sks Hulls.

Elev. 1768'

Anhydrite 540'

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 PM Day: 24 Month: July Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 288' w/260 sks. 4 1/2" set at 3608' w/200 sks.
Open hole 312'. Plugged bottom w/25 sks cement. Shot pipe 6 times and re-
covered 0'. Pulled 300' of 2 1/2" tubing. Ran fishing tools 4 times, pulled
1 - 6" - 1 - 30" - 1 - 36' and left last fish in hole and 298' w/9 joints 2" tubing
on top of fish and cannot be fished. Ran 1" tubing to 700' and spotted 25 sks
cement. Hooked to 4 1/2" and pumped 312 sks cement w/500 Psi. 8 5/8" cement
to surface after circulated.

Remarks: 8-18-87 AUG 18 1987
(If additional description is necessary, use BACK of this form.)

INVOICED (10/10/87) observe this plugging.

By B. J. Titan
DATE

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck
CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 17876