

2 070139

1-9

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 159-01,469.0001  
NE, SEC. 22, T 20 S, R 10 W&E  
feet from N/S section line  
feet from W/E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 8383  
Operator: Four State Petroleum, Inc.  
Name & Address: P. O. Box 391  
Hutchinson, KS 67504-0391

Lease Name Gill Well # 3  
County Rice 110.27  
Well Total Depth 3393 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8-5/8 feet 190

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 Day: 9 Month: 1 Year: 19 89

Plugging proposal received from Dale Fulls

(company name) Kelso Casing (phone) 316-938-2457

were: Sand bottom to 2290' w/5 sx

35 sx @ 900'

35 sx @ 800'

270' to 0

Gel spacers between plugs

RECEIVED  
STATE CORPORATION COMMISSION  
STAFF CORPORATION

JAN 1 8 1989

CONSERVATION DIVISION

W.K. Wichita, Kansas

(TECHNICIAN)

Plugging Proposal Received by

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 1:40 Day: 9 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 2290' w/5 sx - pulled pipe to 900' -

pumped 35 sx - pulled pipe to 800' - pumped 35 sx plug - pulled pipe to 270'

& pumped cement to surface with 100 sx - pumped gel spacers between plugs -

used 60/40 2% - pumped by Allied #5354

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 1-20-89

INV. NO. 23736

Signed

(TECHNICIAN)