

1-21-88

6 070626

API NUMBER 15-009-19490.0001

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C E/2 SW SW, SEC. 7, T 20 S, R 11 W/5

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

_____ feet from S section line

_____ feet from E section line

Lease Name Koch Well # D-0-2 SWD

Operator: Phillips Petroleum Co.

County Barton 127.63

Name &

Address Route #3 Box 20A

Well Total Depth 3927 feet

Great Bend, Ks. 67530

Conductor Pipe: Size 0 feet

Surface Casing: Size 10 3/4 feet 108

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan Kincaid Well Service License Number _____

Address 1710 East 10th Street Hays, Kansas

Company to plug at: Hour: 11:00 A.M. Day: 21 Month: Jan Year: 1988

Plugging proposal received from Jim Tarphing

(company name) Phillips Petroleum (phone) 316-793-8421

were: 10 3/4" 108' S.P. cwc w/125 sks; 7" csg set at 3324' w/75 sks, 5 1/2" csg.

from surface to unknown; 5 1/2" liner 3186' to 3340', 5 1/2" liner 3869' - 3929'. Great Guns

Perf at 150' and 545'. Possibility of cmt in annulus. Open hole 3340' - 3927'. Proposal

500 sks plus 60/40 Poz 6% Gel 2 sks Celloflake. Load and pressure both annulus with cement,

Run tubing to T.D. and circulate cement. Then, squeeze.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN) mjs

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:00 PM Day: 21 Month: Jan Year: 1988

ACTUAL PLUGGING REPORT Ordered 500 sks 50/40 Poz 6% Gel 2 sks Celloflake. Spotted

and displaced with tubing; tag bottom with tubing at 3367'; at 3334' spot and displace

100 sks cement w/1 sk Flocele; at 2577' cwc w/400 sks cmt. Returned for 200 sks cement;

Then squeezed 5 1/2" casing w/125 sks cement. Cement circulated after first 100 sks; 10"-7" annulus.

Pressured 5 1/2" and 7" annulus to 550 Psig. No cement; Pumped 75 sks cement in 10 3/4 and

7" annulus. Max pressure 160 Psig. Shut in at 160 Psig.

Remarks: Cemented by B. J. Titan

(If additional description is necessary, use BACK of this form.) 1-27-88 27.1988

INVOICED

DATE 1-28-88

INV. NO. 19697

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt

FORM CP-2/3
Rev. 01-84 LR