

2-19

6-050103

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-22,058-0000

SW NE SW /4 SEC. 7, 20 S, 11 W
1650 feet from S section line
3360 feet from E section line

Operator license# 5030

Lease Schartz well # 1

Operator: Vess Oil Corporation

County Barton

Address: 8100 E 22nd Street North
Bldg 300
Wichita, Kansas 67226

Well total depth 3300 feet ^{107.25}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 302 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: L. D. Davis License# 6039

Address: Route 1, Box 183-B Great Bend, Kansas 67530

Company to plug at: Hour: PM Day: 19 Month: February Year: 1993

Plugging proposal received from: L. D. Davis

Company: L. D. Davis phone: 316-793-3051

Were: 4 1/2" set at 3326 with 100 sx. Open hole from 3326 to 3330'.
Plug back with sand to 3200', bale dump 5 sx cement. Shoot and pull casing to 1400', cement as you pull rest of casing.

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:45 PM, Day: 19, Month: February, Year: 1993

Actual plugging report: Shot pipe at 2500', not able to pull. Shot again at 1770', pull to 1400'. Pumped 150 sx 60/40 poz, 6% gel, pull to 700', pump 75 sx 60/40 poz, 6% gel. Pull 360' pipe, pump 75 sx 60/40 poz, 6% gel, circulated cement. Pull 340' pipe, topped off with 20 sx 60/40 poz, 6% gel. Plug down at 3:45 PM

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Allied Cementing over hole.

MAR 12 1993

I did [XX] / did not [] observe the plugging.

Bruce D. Basye
CONSERVATION DIVISION
Wichita, Kansas

Bruce D. Basye
(agent)
Form CP-2/3

INVOICED

DATE 3-16-93

INV. NO. 37464

110