

15.009.22547.0000

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-22,514
NE-SW-SW, Sec. 7, T 20S, R 11 W/E

_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 5544

Lease Name HOCH Well # 2

Operator: TOMASON OIL COMPANY
Name & 2700 OHM. #A
Address HAYS, KANS. 67601

County BARTON

Well Total Depth 3321 feet

Conductor Pipe: Size 0 feet 0

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CEMENTING CO License Number _____

Address BOX 31 332 WEST WICHITA, RUSSELL, KS. 67665

Company to plug at: Hour: 2:00 PM Day: 9th Month: NOV. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO STEVE TOMASON

(company name) TOMASON OIL COMPANY (phone) 913-628-3069

were: 8 5/8 - 328^{EL} DR. - 1/250ST CMT. - 4 1/2" SET @ 3323ST - 1/125ST CMT.

PERF'S - TOP 3321^{EL} PLUG. BOTTOM - SET CAST IRON PLUG @ 3280^{EL}

AND 1/5ST CMT. - SHOT TWICE RECOVERED 1450^{EL} - ORDER 165ST

5 1/2ST BORDIN 4% GEL - 3% PH-CL - 20ST GEL - 5ST HULL'S - AND 8 5/8" PLUG.

PUMP IN 8 5/8" - 4ST HULL'S - 15ST GEL - 1/2ST HULL'S - 25ST CMT. - 5ST GEL - 1/2ST HULL'S.

REL-PLUG. AND 140ST CMT.

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:45 PM Day: 9th Month: NOV. Year: 1982

ACTUAL PLUGGING REPORT

PUMPED IN 8 5/8" CCG. - 4ST HULL'S - 15ST GEL - 1/2ST HULL'S

25ST CMT. - 5ST GEL 1/2ST HULL'S. RELEASE PLUG.

AND 140ST CMT. MAX PRESSURE 250 PSI

CEMENTED BY HULLED CMT.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1982

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

INVOICED

11-24-82

DATE 1738-W

Signed [Signature]
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82