

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22059-00-00
Spot: CE2E2NW Sec/Twnshp/Rge: 7-20S-11W
3960 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: SCHARTZ A Well Number: 1
County: BARTON Total Vertical Depth: 3334 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 8108.36
Surface Casing: Size 8.625 feet: 306 250 sxs cmt
Production: Size 5.5 feet: 3330 100 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/04/2002 9:00 AM
Plug Co. License No.: 5030 Plug Co. Name: VESS OIL CORPORATION
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Perfs - LKC 3314' - 3319'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/04/2002 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded bottom to 3250' with 5 sxs cement using dump bailer.
Shot casing at 2210'.
Pulled casing to 1340' and pumped 95 sxs with 300# hulls.
Pulled casing to 603' and pumped 40 sxs with 100# hulls.
Pulled casing to 250' and pumped 40 sxs to circulate cement to surface.
POOH. Pulled rest of casing and topped off with 20 sxs.
Hole standing full of cement.

RECEIVED
APR 15 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET#9094.

Plugged through: CSG

District: 04

Signed *Pat Staab*

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-16-02

INV. NO. 2002061663

APR 08 2002

PETROLEUM ENERGY INC

710 ONE TWENTY BLDG

WICHITA, KS 67202

CONTR WHITE & ELLIS DRLG

#1 SCHARTZ "A"

7-20-11W
C E/2 E/2 NW

CTY BARTON

GEOL

FIELD CHASE-SILICA

E 1789 KB CM 9/5/80 CARD ISSUED 11/13/80 IP P 108 BOPD NO WTR
1784 GL

API 15-009-22,059

ARB OH 3330-3334

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM.
HEEB	2948	-1159	
TOR	2964	-1175	
DOUG	2980	-1191	
BR LM	3071	-1282	
LANS	3089	-1300	
ARB	3329	-1540	
RTD	3334	-1545	

8 5/8" 306/250sx; 5 1/2" 3330/100sx

DST (1) 3206-3316/30-30-30-30, REC
60' GIP, 60' OCM, 160' SG & OCM,
SIP 198-98#, FP 85-77/85-80#

DST (2) 3329-3334/30-30-30-30, REC
180' GIP, 350' CL GSY OIL, 70' MGO,
NS, SIP 1104-1080#, FP 94-134/
171-183#

MICT - CO, (ARB OH), SWB 3 1/2 BOPH/3HRS
NW, NAT, POP, P 108 BOPD NW

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

15000000