

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-19006-00-01  
Spot: SESESW Sec/Twnshp/Rge: 11-20S-10W  
4950 feet from N Section Line, 2310 feet from W Section Line  
Lease/Unit Name: KITSY-MINOR Well Number: 3  
County: RICE Total Vertical Depth: 3342 feet

Operator License No.: 31940  
Op Name: B & B OIL  
Address: 212 WEST AVE. "A" PO BOX 447  
CHASE, KS 67524

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 205 175 SX CMT  
Production: Size 4.5 feet: 3340 150 SX CMT \$108.62  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/19/2001 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL INC. Phone: (316) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/20/2001 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded 50' above bottom of 4 1/2" prod. Casing and put 4sxs cement on top. Shot off 4 1/2" prod. Casing @ 1700' and attempted to pull-salvaged approx 135'. Had to run tubing down hole to approx. 1300' and pump 35sxs then perforate at 900' and pump 35sxs then lower perf gun to 250' to perforate and circulate cement to surface. 145sxs.

RECEIVED  
KCC DISTRICT #2

NOV 20 2001

WICHITA, KS

Remarks: 60/40 POZ-MIX 4% GEL. ALLIED CEMENT TICKET # 8800

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 12-3-01

INV. NO. 2002061000