

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- OWWO 6-30-83 *R*

NE 5ENE, Sec. 11, T 20 S, R 10 (W/E)

3630 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5990

Lease Name Stickney "D" Well # 1OWWO

Operator: Paul Bandy Oil Producer  
Name & Address: Box 364  
Canton, Kansas 67428

County Rice

Well Total Depth 3356 feet 109.07

Conductor Pipe: Size        feet       

Surface Casing: Size 8 5/8 feet 211-135 sacks ✓

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D&A       

Other well as hereinafter indicated       

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 10:00 A Day: 23 Month: January Year: 1985

VERBAL PLUGGING ORDERS GIVEN TO Bub Brenneman

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 3240' and cement with 4 sacks.

Squeeze hole with 5 sacks hulls, 20 sacks Bentonite, and  
100 sacks 50/50 Pozmix w/4% gel. Pump into 8 5/8" surface  
casing.

Signed *Arthur J. Lomen*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part        None       

Operations Completed: Hour: 11:00 AM Day: 23 Month: January Year: 1985

ACTUAL PLUGGING REPORT Hole Filled with Sand to 3240' and cemented  
with 4 sacks dumped on sand. Hole squeezed with 5 sacks  
hulls, 20 sacks Bentonite, and 100 sacks 50/50 Pozmix w/4%  
gel pumped into 8 5/8" surface casing.

RECEIVED  
STATE CORPORATION COMMISSION

1-29-85 JAN 29 1985

Remarks: 1712' of 4 1/2" casing recovered 4 1/2" - 3356' - 135 sacks  
Conservation Division  
Wichita, Kansas

Allied Cementing Co, Inc. Ticket # 2441

Max Press. 600 PSIG Close in 200 PSIG

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did) did not) observe this plugging.

INVOICED

DATE 1-31-85

INV. NO. 6750

Signed *Arthur J. Lomen*  
(TECHNICIAN)