

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

January 21, 1965

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co has this
 date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name: Guldner Well No. 1

Location: NE NE NE Sec. 5 Twp. 18 Rge. 9 (E) (W) X

County Rice Total Depth 3253' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3235' and cement with 3 sacks.

Fill hole with mud to 240'. Set rock bridge from 240' to

230' and cement hole with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with

10 sacks cement.

Very truly yours,

Arthur J. Loman
 Conservation Division Agent

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 1 1965
 2-1-1965
 CONSERVATION DIVISION
 Wichita, Kansas