

State of Kansas



15.159.30210.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
APR 11 1966
CONSERVATION DIVISION
Wichita, Kansas
4-11-1966
April 7, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Flake of Woodman-Tannitti Drlg. Co. has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Audley Ogden

Complete Address: P.O. Box 301, Hutchinson, Kansas

Lease Name: Remmert Well No. 1

Location: NE SW NE Sec. 3 Twp. 18 Rge. 9 (E) (W) X

County Rice Total Depth 3270' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogden was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and 1/4 sack hulls to 240' and cement hole with 20 sacks through drill pipe. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent