

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 5, 1966 9-13-1966

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Flake of Woodman-Tannitti has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman-Tannitti

Complete Address: 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name: Baldwin Well No. 1

Location: C SW NE Sec. 29 Twp. 18 Rge. 8 (E)(W) X

County Rice Total Depth 3441' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

Fill hole with mud to 195'. Push plug and 1/4 sack hulls to 195' and

cement hole with 20 sacks through drill pipe. Fill hole with mud to

40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent