

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

March 5, 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Paul Stephens of Buffalo Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Company, Inc.

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name: Boldt Well No. 1

Location: SE NE NW Sec. 29 Twp. 18 Rge. 9 (E) (W)

County: Rice Total Depth: 3319'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Stephens was instructed to plug the well as follows:

8 3/4" - 205' - 170 sacks 50/50 Pozmix 2% gel 3% oil. Circulate hole and fill with mud. Pump 60 sacks cement through drill pipe at 450'. Pump 30 sacks cement through drill pipe at 200'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 10 sacks cement.

Orders by Marion Schmidt

Very truly yours,

Stella J. Larson
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1982
CONSERVATION DIVISION
Wichita, Kansas