

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 18, 1966

RECEIVED
NOV 22 1966
CONSERVATION DIVISION
Wichita, Kansas
11-22-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Duke Burt of Burt Drilling Company has this date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: Hummon Oil, Incorporated

Complete Address: 821 Union Nat'l Bldg., Wichita, Kansas

Lease Name: Potter Well No. 1

Location: C SW SE NW Sec. 11 Twp. 19 Rge. 8 (E) (W) X

County Rice Total Depth 3335' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burt was instructed to plug the well as follows:

Fill hole with mud to 190'. Push plug and 1/4 sack hulls to 190' and
cement hole with 20 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent