

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED August 14, 1963
 STATE CORPORATION COMMISSION

AUG 19 1963

8-19-1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Otto Berens of Rex & Morris Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Berens guarantees payment of the plugging fee.

Operator's full Name: Rex & Morris Drilling Company

Complete Address: Box 334, El Dorado, Kansas

Lease Name: Burdette "A" Well No. 1

Location: E/2 SW SE Sec. 1 Twp. 19 Rge. 8 (E) (W) X

County Rice Total Depth 3274' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Berens was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 210'. Push
plug and $\frac{1}{4}$ sack hulls to 210' and cement with 20 sacks
through drill pipe. Fill hole with mud to 35'. Push plug
and $\frac{1}{4}$ sack hulls to 35' and cap hole with 10 sacks cement.
Bridge rathole, and cement with 2 sacks.

Very truly yours,

Alfred J. Tomasa
 Conservation Division Agent