

State of Kansas



WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JOHN C. WOELK Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

RECEIVED  
AUG 1 1966

CONSERVATION DIVISION  
Wichita, Kansas

8-1-1966

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

July 22, 1966

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. George Klein of Messman-Rinehart Oil Co. has this date requested permission to plug the following described well:

Mr. Klein guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza, Wichita, Kansas

Lease Name: Schrader Well No. 1

Location: C NW SW Sec. 1 Twp. 19 Rge. 7 (E) (W) X

County Rice Total Depth 3530' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Klein was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and cement hole with 20 sacks through drill pipe. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cement hole to base of cellar with 10 sacks.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

*William L. Mitchell*  
 Conservation Division Agent