

State of Kansas



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 18 1968  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

March 13, 1968

3-18-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Lahar of B & B Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Allison & Black

Complete Address: 1415 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Manke Well No. 4

Location: NW SW <sup>SE</sup> SW Sec. 20 Twp. 18 Rge. 10 (E) (W) X

County: Rice Total Depth 3275' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Lahar was instructed to plug the well as follows:  
Circulate heavy mud. Pump 25 sacks cement through drill pipe at 500'.  
Push plug and 1/4 sack hulls to 225'. Pump 25 sacks cement through drill  
pipe at 225'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls  
to 40' and cap hole with 10 sacks cement.  
Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent