

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 21, 1963

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1963

CONSERVATION DIVISION
Wichita, Kansas

11-26-1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. E. J. Bishop of Inger Oil Company has this
date requested permission to plug the following described well:

Mr. Bixhop guarantees payment of the plugging fee.

Operator's full Name: Inger Oil Company

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name: Dressler Well No. 1

Location: NE NE NE Sec. 27 Twp. 19 Rge. 8 (E) (W) X

County Rice Total Depth 3500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 200'. Push
plug and $\frac{1}{4}$ sack hulls to 200' and cement with 25 sacks
through drill pipe. Fill hole with mud to 40'. Push plug
and $\frac{1}{4}$ sack hulls to 40' and cap hole with 10 sacks cement.
Bridge rathole, and cement with 2 sacks.

Very truly yours,