

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 3, 1965

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1966

CONSERVATION DIVISION
Wichita, Kansas

1-6-1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Roy Cook of Imperial Oil Company has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company

Complete Address: 780 Fourth Nat'l Bldg., Wichita, Kansas

Lease Name: Smith Well No. 2

Location: NW SE SE Sec. 26 Twp. 19 Rge. 8 (E)(W) X

County Rice Total Depth 3406' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

Fill hole with mud to 275'. Push plug and 1 sack hulls to 275' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Arthur J. Thomas
Conservation Division Agent