

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

✓

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15-159-21,225.00.00

Operator's Full Name Energy Oil & Gas

Complete Address _____

Lease Name Steffen Well No. B-1

Location SE SW NW Sec. 26 Twp. 18 Rge. 9 (~~East~~) (West)

County Rice Total Depth 3279'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. and Allied Cementing Co., Inc.

Address Box 823, Great Bend, Kansas License No. _____

Operation Completed: Hour: 10:40 PM Day: 20 Month: July Year: 19 81

Plugging Operations attended by Agent? All _____ Part _____ None X

The above well was plugged as follows: 8-5/8"-238'-175 sacks

Hole circulated and filled with mud. 50 sacks 50-50 Pozmix with 2% gel
and 3% cal. chl. pumped through drill pipe at 540'. 30 sacks cement
pumped through drill pipe at 240'. Plug and 1/2 sack hulls pushed to 40'
and hole cemented to base of cellar with 10 sacks cement. Rathole
cemented with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1981 7-23-1981
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 8-25-81

INV. NO. 6220-w