

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-159-21,409 ✓

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Rains + Williamson Oil Company, Inc.

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name Boldt Well No. 1.

Location SE NE NW Sec. 29 Twp. 18 Rge. 9 (~~East~~) (West)

County Rice Total Depth 3319'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Buffalo Drilling Co, Inc. and Allied Cementing Co, Inc.

Address 435 Page Court, 220 W. Douglas, Wichita, Kansas License No. _____

Operation Completed: Hour: 7:30 PM Day: 5 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

Hole circulated and Filled with mud. 60 sacks cement pumped through drill pipe at 450'. 30 sacks cement pumped through drill pipe at 200'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

Cement used: 50/50 Pozmix w/2% gel and 3% C.C.

Amount of Surface Casing: 8 5/8" - 205' - 170 sacks 50/50 Pozmix w/2% gel + 3% C.C.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
3-10-82

MAR 10 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 3-12-82

INV. NO. 9634-W