

State of Kansas



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date September 25, 1958, authorized the following plugging operation:

Operator's Full Name: Strata Drilling Inc.Complete Address: Box 355, Great Bend, KansasLease Name: HaxtonWell No. 1Location: NW-SE-SWSec. 28Twp. 18Rge. 9(E) (W) County: RiceTotal Depth: 3285Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 250' with heavy
mud. Push plug and $\frac{1}{4}$ sack hulls to 250'. Cement with 20 sacks
thru drill pipe. Fill hole to 35' with heavy mud. Push plug
and $\frac{1}{4}$ sack hulls to 35' and cement with 10 sacks.

2 sacks in rathole.

Very truly yours,

Signed: Jewel M. Ogden

Conservation Division Agent

RECEIVED
 STATE CORPORATION COMMISSION

OCT 30 1958

10-30-1958
 CONSERVATION DIVISION
 Wichita, Kansas