

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rice

Location: NW-SE-SW Sec. 29 Twp. 18 Rge. 9 (E) (W) X

Name of Field: Wildcat Total Depth: 3285

I have this date completed supervision of plugging of:

Lease Name: Haxton Well No. 1

Operator's Full Name: Strata Drilling Inc.

Complete Address: Box 355, Great Bend, Kansas

Plugging Contractor: Operator

Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 10:00 AM Day 26 Month September Year 1958

The above well was plugged as follows:

Heavy mud circulated. Hole filled to 250' with heavy mud. Plug and
1/2 sack hulls pushed to 250'. Cemented with 20 sacks thru drill pipe.

Hole filled with heavy mud to 35'. Plug and 1/2 sack hulls pushed to 35'
cemented to bottom of cellar with 10 sacks. Rathole cemented with 2 sacks.

Signed: *Arthur J. Leonard*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 29 T. 18 R. 9W
BOOK PAGE 133 LINE 34

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1958
CONSERVATION DIVISION
Wichita, Kansas
10-30-1958