

ry
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1966

CONSERVATION DIVISION
WICHITA, Kansas

9-20-1966

Operator's Full Name Imperial Oil Company

Complete Address: 780 Fourth Nat'l Bldg., Wichita, Kansas

Lease Name Miller Well No. 1

Location C NE NE Sec. 13 Twp. 19 Rge. 8 (E) (W) X

County Rice Total Depth 3509'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Operator

Address: License No.

Operation Completed: Hour 5 PM Day 11 Month September Year 1966

The Above well was plugged as follows:

Hole filled with mud to 300'. Plug and $\frac{1}{4}$ sack hulls pushed to 300' and hole cemented
with 20 sacks through drill pipe. Hole filled with mud to 40'. Plug and $\frac{1}{2}$ sack hulls
pushed to 40' and hole cemented to base of cellar with 10 sacks.
Rathole bridged, and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: *Arthur J. Tomad*
Well Plugging Supervisor

9/20/66
3956-W