

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 137-2

LOCATION NW-NE-SE

SEC. 14 TWP. 19 RGE. 6W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Green

Operator G.M.R. Oil Co. Address Box 1003 Wichita Kans.

Field \_\_\_\_\_ County Rice

Total Depth 3410 Feet.

Plugging Contractor G.M.R. Oil Co.

Plugging Contractor's License No. # 20

Address Box 1003 Wichita Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8 @ 157' C.W.C. Oil String 4 1/2" @  
3380' Set With 100 SX of Cem. Filled hole back with  
sand to 3370' and dumped 4 SX of Cem. Shot off and  
pulled 4 1/2" casing. Filled hole with mud to 250'  
set 10' rock bridge and dumped 20 SX of Cem. with  
dump bails. Filled hole with mud to 40' set  
rock bridge and 10 SX of mixed Cem. to surface.  
Wells Completed.

Warren H. Horner  
District Conservation Agent

Date 10-23-53

PLUGGING  
FILE SEC. 14 T. 19 R. 6W  
BOOK PAGE 137 LINE 2

RECORDED  
STATE OF KANSAS  
OCT 23 1953  
CONSERVATION DIVISION  
WICHITA, KANSAS

10-27-1953