


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800-Eitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County. Sec. 9 Twp. 18 Rge. 8W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NW NE
Lease Owner Dozier Oil Company
Lease Name Schill Well No. 2
Office Address 1307 Union Nat'l. Bank - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed April 11, 1952 19____
Application for plugging filed January 11, 1955 19____
Application for plugging approved January 12, 1955 19____
Plugging commenced January 20 1955
Plugging completed January 24 1955
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3260 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285'	None
				5-1/2"	3257'	2505'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was plugged back to 3235' and casing was perforated from 3215' to 3230'. Filled hole with sand from 3235' to 3205' and ran 6 sacks of cement. Mudded hole to 290', set a 10' rock bridge and ran 15 sacks of cement. Mudded hole to 15' and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.
R. M. Beck, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. M. Beck Jr.
1307 Union National Bank Bldg, Wichita 2 (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January, 1955

My commission expires November 19, 1958

Virginia Van Meter Notary Public.

PLUGGING
WELL SEC. 9 T. 18 R. 8W
BOOK PAGE 90 LINE 25

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1955
1-27-1955
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas


15.159.06257.00.00

Company- DOZIER OIL COMPANY
 Farm- Schill No. 2

SEC. 9 T. 18 R. 8W
 NE NW NE

Total Depth. 3260 RB
 Comm. 4-3-52 Comp. 4-11-52
 Shot or Treated.
 Contractor. Stag Drilling Co.
 Issued. 7-12-52

County Rice
 KANSAS



Elevation. 1766

CASING:
 8 5/8" 215'
 5 1/2" 3260'

Production. D.D. 949 bbls, no wtr

All measurements from top of rotary bushing: Figures Indicate Bottom of Formations.

surface soil 215
 red bed, shale, shells 340
 shale shells 850
 salt 1070
 lime, shale 1420
 sandy lime 1495
 lime shale 1905
 shale shells 2460
 shale, lime 2510
 lime 2711
 shale 2715
 lime, shale 2838
 lime 3167
 lime shab 3218
 conglomerate 3256
 arbuckle 3260
 Total Depth

Tops: Scout.
 Heebner 2711
 Kansas City 2861
 Congl. 3218
 Arbuckle 3256

PLUGGING
 FILE SEC 9 T 18 R 8W
 BOOK PAGE 90 LINE 25