

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 8 Twp. 18 Rge. 8 El (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE

Lease Owner Isern Brothers etal

Lease Name Hays Well No. 1

Office Address Box 45, Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 8, 1956

Application for plugging filed October 8, 1956

Application for plugging approved October 8, 1956


Plugging commenced October 8, 1956

Plugging completed October 8, 1956

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3495 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	<u>Surface Pipe</u>	<u>0</u>	<u>240'</u>	<u>8-5/8"</u>	<u>240'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 225'.
Bridged hole at 225'. Ran 15 sacks
cement 225' up. Bridge hole at 25',
ran 5 sacks cement. Plug 25' to
base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

10-13-1956

Name of Plugging Contractor Isern Drilling Company
Address Box 45, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON
M. M. Shropshire (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Shropshire

Lyons, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1956

My commission expires Feb. 10, 1959.

George A Meyer
Notary Public.

PLUGGING
FILE SEC 8 T 18 R 8 W
BOOK PAGE 107 LINE 16

WELL LOG

ISERN BROTHERS ETAL, Owner - Hays #1
 NW/4 NW/4 NE/4 Section 8, Township 18, Range 8W,
 Rice County, Kansas

ELEVATION: 1772 KB

Figures indicate bottom of formation
 0 to 345 shale & shells
 355 sand
 370 shale
 450 Red rock
 480 Anhydrite
 900 shale & shells
 1045 salt
 1290 shale & shells
 1455 lime & shale
 1480 sand
 1490 lime & shale
 1520 sand
 1945 lime & shale
 2495 shale & shells
 3495 lime & shale
 3495 Rotary Total
 Depth D&A

PIPE RECORD:

8-5/8" set at 240'
 Cemented with 150 sacks
 September 29, 1956

TOPS: RBM

Heebner 2756
 Brown Line 2874
 Lansing 2904
 Conglomerate Sand 3278
 Simpson Sand 3425
 Arbuckle 3475

Rotary Commenced 9-29-56
 Completed 10-8-56

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 13 1956
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS :)
 COUNTY OF BARTON :) SS

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 9th day of October, 1956

PLUGGING
 FILE SEC 8 T. 18 R. 8W
 BOOK PAGE 107 LINE 16

George A. Meyer
 Notary Public

My commission expires Feb. 10, 1959.