

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rice SEC. 1 TWP. 18 RGE. 8 E/W
Location as in quarters or footage from lines:
NW SW SW 940' FSL 405' FWL

Locate Well
correctly on above
Section Platt.

Lease Owner Prospect Oil & Gas Co.
Lease Name Choate Well No. 1
Office Address Rt #1 Box 15 Dorrance, Kansas 67634
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 5-23-83
Application for plugging filed 5-23-83
Plugging commenced 5-23-83 1:15 pm
Plugging completed 5-23-83 6:00 pm
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Tittle
Producing formation _____ Depth to top _____ bottom _____ T.D. 3375
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole to 500' with heavy mud and mixed 50 sacks of cement and pumped in hole thru
drill pipe.

Filled hole to 250' with heavy mud and mixed 30 sacks of cement and pumped in hole thru
drill pipe.


Filled hole to 40' built bridge pushed down plug and mixed 10 sacks of cement and pumped
into hole to bottom of cellar; mixed 10 sacks and pumped into rat hole.

All cement uses was 50-50 Poz Mix 6 % Gel 3% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Revlin Drlg., INC.

STATE OF Kansas COUNTY OF Russell, ss.
Stanley C. Lingreen (employee of owner) or ~~(owner or operator)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Stanley C. Lingreen
Box 293 Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1983

Paula J. Gibson
RECEIVED
STATE CORPORATION COMMISSION Notary Public.

My Commission expires: November 10, 1984

JUN 15 1983

CONSERVATION DIVISION
Wichita, Kansas
6-15-1983