


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

RICE County. Sec. 35 Twp. 18S Rge. (E) 7 (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner JOHN E. HILL
Lease Name EDGAR MABRY Well No. 1
Office Address 315 EAST FIRST, SOUTH HUTCHINSON, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 2-5 19 64
Application for plugging filed (PHONE 1-30-64) 2-5 19 64
Application for plugging approved (PHONE 1-30-64) 2-5 19 64
Plugging commenced 1-30 19 64
Plugging completed 1-30 19 64
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN, HOLYROOD, KANSAS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3540 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	204'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 195 FEET. SET FIRST PLUG @ 195 FEET WITH 20 SACKS CEMENT.
FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG @ 40 FEET WITH 10 SACKS CEMENT.
TWO SACKS CEMENT IN RAT HOLE.

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1964

2-6-1964

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor GABBERT-JONES INC. (If additional description is necessary, use BACK of this sheet)
Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E.E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E.E. Hall

514 ORPHEUM BLDG., WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 5TH day of FEBRUARY, 1964

Vera A. McKenzie Notary Public.

My commission expires OCTOBER 2, 1967



GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

EDGAR MABRY #1
 C SW SW SECTION 35-18S-7W
 RICE COUNTY, KANSAS

COMMENCED: JANUARY 21, 1964
 COMPLETED: JANUARY 30, 1964

OPERATOR - JOHN E. HILL

DEPTH		FORMATION	REMARKS
FROM	TO		
0	30	SAND ROCK	RAN 10 JOINTS 8-5/8" CASING, SET @ 204' W/190 SACKS CEMENT
30	204	CLAY	
204	915	SHALE, SHELLS AND RED BED	<p style="text-align: center;">RECEIVED STATE CORPORATION COMMISSION</p> <p style="text-align: center;">FEB 6 1964</p> <p style="text-align: center;">CONSERVATION DIVISION Wichita, Kansas</p>
915	995	SHALE AND SHELLS	
995	1015	ANHYDRITE	
1015	1225	SHELLS - SHALE	
1225	2300	LIME AND SHALE	
2300	2400	LIME	
2400	2535	LIME AND SHALE	
2535	2605	LIME	
2605	2857	LIME AND SHALE	
2857	3120	LIME	
3120	3208	CORING	
3208	3405	LIME	
3405	3455	LIME AND SHALE	
3455	3486	SAND AND SHALE	
3486	3540	SHALE	
3540	TD		

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE C SW SW SECTION 35-18S-7W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 3RD DAY OF FEBRUARY, 1964, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vira A. McKenzie
 VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1967