

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

RICE County. Sec. 33 Twp. 18S Rge. (X) 7 (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner J. L. CHEW

Lease Name ORM Well No. 1

Office Address Box 526, LYONS, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 2-18 19 64

Application for plugging filed LETTER (2020-64) 2-18 19 64

Application for plugging approved 2-18 19 64


Plugging commenced 2-18 19 64

Plugging completed 2-18 19 64

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN, HOLLYROOD, KANSAS

Producing formation Depth to top Bottom Total Depth of Well 3520 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	217	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 200 FEET. SET FIRST PLUG AT 200 FEET WITH 20 SACKS

CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG AT 40 FEET WITH

10 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1964 2-21-1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES INC.

Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

514 ORPHEUM BLDG., WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 20TH day of FEBRUARY, 1964

My commission expires OCTOBER 2, 1967

VIRA A. MCKENZIE Notary Public.

GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

ORM #1
 C NE NE SECTION 33-188-7W
 RICE COUNTY, KANSAS

COMMENCED: FEBRUARY 10, 1964
 COMPLETED: FEBRUARY 18, 1964

OPERATOR - J. L. CHEW


<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	105	SANDY CLAY	
105	217	SHALE W/ SHELLS	RAN 10 JOINTS 8-5/8 INCH CASING, SET @ 217' W/ 190 SACKS CEMENT
217	1010	CLAY, SHELL & RED BED	
1010	1031	SHELL & LIME	
1031	1410	SHALE & SHELLS	
1410	1570	SHALE & LIME	
1570	1815	SHALE & LIME STREAK	
1815	2090	SHALE	
2090	2475	LIME & SHALE	
2475	2810	LIME	
2810	2940	SHALE & BROWN LIME	
2940	3218	LIME	
3218	3310	LIME & SHALE	
3310	3520	LIME	
3520	TD		DRY & ABANDONED

RECEIVED
 STATE CORPORATION COMMISSION

FEB 21 1964

CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C NE NE SECTION 33-188-7W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.




 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE ON THIS 20TH DAY OF FEBRUARY, 1964, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.



 VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1967