


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County, Sec. 29 Twp. 18 Rge. 9 W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
SW NW SE

Lease Owner F & M Oil Co., Inc.
Lease Name Lance Well No. 1
Office Address 505 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed September 13 19 76
Application for plugging filed September 13 19 76
Application for plugging approved September 13 19 76
Plugging commenced September 13 19 76
Plugging completed September 13 19 76
Reason for abandonment of well or producing formation _____

Dry Hole
If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3305'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug @ 500' w/40 sacks cement thru drill pipe.

Middle plug @ 240' w/25 sacks cement thru drill pipe.

Top plug @ 40' w/1/2 sack hulls and 10 sacks cement.

2 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.
Leonard Williamson (employee of owner) or (XXXXXXXXXXXXXXXXXX)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
Box 823, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 76

Dorothy M. Hague
Notary Public.

My commission expires April 11, 1978

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1976
9-15-1976
CONSERVATION DIVISION
Wichita, Kansas

WILLIAMS HILL LOG

DATE COMMENCED: September 6, 1976
 DATE COMPLETED: September 13, 1976

F & H Oil Co., Inc.
 LAND # 1
 S 1 N 1 E 3
 Sec 29-T10-R9
 Rice County, Kansas

ELEVATION: 1720 K.F.

0 - 253' Surface Soil, Shale, Sand streaks
 253 - 374' Red Bed
 374 - 414' Anhydrite
 414 - 1175' Shale, Shells
 1175 - 2751' Lime and Shale
 2751 - 2754' Shale
 2754 - 2792' Lime and Shale
 2792 - 2878' Shale
 2878 - 2896' Lime and Shale
 2896 - 3196' LIME
 3196 - 3250' Lime and Shale
 3250 - 3305' Dolomite
 3305' STD

FORMATION TOPS

Anhydrite	374
Hedden	2751
Douglas	2792
Drown Lime	2878
Kansas City	2896
Base K.C.	3196
Arbuckle	3250
RFD	3305

SURFACE PIPES:
 Not used 3 5/8", 23' pipe @ 252'
 w/160 sacks Common, 2' Gel, 3' cc.

AFFIDAVIT

STATE OF KANSAS }
 COUNTY OF RICE } ss.

Leonard Williamson, of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 14th day of September, 1976.

Rosemary M. Hague
 Notary Public

My Commission Expires: April 11, 1978

RECEIVED
 CONSERVATION COMMISSION

SEP 15 1976

CONSERVATION DIVISION
 Topeka, Kansas