

WR 6

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 11 Twp. 19 Rge. 8 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE of NE 1/4

Lease Owner The Wood River Oil & Refining Co. Inc.

Lease Name Gray

Well No. 1

Office Address 335 W. Lewis St. Wichita Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 21, 1944

19

Application for plugging filed January 25, 1945

19

Application for plugging approved January 25, 1945

19

Plugging commenced February 2, 1945

19

Plugging completed February 7, 1945

19

Reason for abandonment of well or producing formation Unable to obtain

production of oil or gas in commercial quantities.

If a producing well is abandoned, date of last production None

19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Durkee

Producing formation Arbuckle

Depth to top 3344

Bottom 3352

Total Depth of Well 3352 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	show gas oil & water	3344	3352	5 1/2"	3344	2549'
				10 1/2"	193	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Nov. 17 '44 Plugged Back to 3300 w/ Lane Wells Bridge Plug

Nov. 18 '44- Pipe Perforated w/ 58 holes from 3148' to 3159'

Feb. 2 '45- Dumped 5 sack cement plug at 3072'

Feb. 3 '45- Run sand line to top cement plug at 3022'

Feb. 4 '45- Attempted sheet pipe off at 3000', 2800', 2700', 2600' and 2550' -- pulled 2549ft.

Feb. 6 '45- Plugged Hole with mud to 300' from surface.

Feb. 7 '45- Set bridge plug at 160' with rock; Dumped 10 sack Cement plug on top of same.

Filled hole with mud to ten feet of top, then dumped 5 sack sack cement plug on top of same for cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Wood River Oil & Refg. Co.

2-28-1945

Address 335 W. Lewis St., Wichita Ks.

STATE OF Kansas, COUNTY OF Sedgewick, ss.

V. E. Wiggins

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 191, McPherson Ks.

(Address)

SUBSCRIBED AND SWORN to before me this 17th day of February 1945

My commission expires

May 12, 1947

Notary Public.

Wood River Oil & Refining Co.
Gray #1

Sec. 11 Twp. 19 Rge. 8
County: Rice, Kansas

Total Depth: 3349'
Comm: 9/29/44 Comp: 11/20/44

Casing
6Jts. 10/3/4" Set at 192'
121 Jts. 5 1/2" Set at 3342'

Cement
125 Sacks
100 Sacks

Formation:	Depth:
Clay	70'
Sand	170
Shale & Shells	200
Clay, Sand, Shells, Shale, RedBed	660
Shale & Shells	890
Salt, Shale, & Shells	1000
Shale & Shells	1070
Anhydrite	1130
Shale, Lime Shells	1220
Shale & Lime	1275
Shale, Lime shells	1460
Sandy Lime & Shale	1540
Lime & Shale	2010
Lime, Shale, Shells	2060
Sand, Shale, & Lime Shells	2110
Shale & Shells	2135
Shale & Lime Shells	2180
Lime & Shale	2205
Shale & Lime Shells	2245
Lime & Shale	2335
Shale & Shells	2415
Lime & Shale	2525
Lime	2585
Lime & Shale	2655
Lime	2685
Lime & Shale	2800
Shale	2865
Lime & Shale	2885
Lime	2992
Lime & Shale	3153
Sand	3156
Lime	3160
Lime & Shale	3200
Shale	3235
Shale & Sand	3279
Lime & Shale	3319
Lime	3321
Sandy Dolomite & Chert	3336
Lime, Shale, & Sand	3347
Lime, Sand	3349
Dense Dolomite	3350 1/2
Green Shale	3352
T D Rotary Tools	3349
T D Cable Tools	3352

11 19 84
2 43

State of Kansas)
Sedgwick County) ss

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 27th day of February, 1945

C. C. Chapman
Ruth H. Glascock
Notary Public