

STATE OF KANSAS
STATE CORPORATION COMMISSION
*Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rice County. Sec. 1 Twp. 19S Rge. (E) 8 (W)
Location as "NE/CNW/SW" or footage from lines E/2 NW SE
Lease Owner Jayhawk Oil Co.
Lease Name Burdette Well No. 1
Office Address 103 One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August 18 19 66
Application for plugging filed May 2 19 69
Application for plugging approved May 4 19 69
Plugging commenced May 9 19 69
Plugging completed May 20 19 69
Reason for abandonment of well or producing formation Uneconomic to produce

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tolman
Producing formation Arbuckle Depth to top Bottom 3287 Total Depth of Well 3287 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250	none
				5-1/2"	3286	2047

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5 1/2' @ 3286' w/75 sks.
Sand 3287'-3275'
5 sacks cement @ 3275'
Shot pipe @ 2741' and spotted oil
Shot pipe @ 2688, 2595, 2402, 2309, 2216, 2123 & 2022'
Rock bridge @ 200-190'
25 sacks cement @ 190'
Mud to 40'
Rock Bridge 40'-30'
10 sks cement 30' to 4' below surface
Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1969
CONSERVATION DIVISION
Wichita, Kansas
6-3-1969

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
210 One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of June, 19 69

My commission expires March 21, 1970
[Signature] Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Jayhawk Oil Company
FARM Burdette "A" NO. 1 OWWO

SEC 1 T. 19S R. 8W
LOC E/2 NW SE

TOTAL DEPTH 3,287'
COMM. 8-15-66 COMP. 8-18-66
SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED

COUNTY Rice
KANSAS

CASING
20 10 5/8" 250'
15 8 5/8" 250'
12 6
13 5 1/2" 3,287'

ELEVATION
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Cement & plug 250
Wash Down 3274
Arbuckle 3287
Rotary T. D. 3287

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1969
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
SEDGWICK COUNTY } SS:

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 29th day of August, 1966.

Geraldine Hays
Geraldine Hays, Notary Public

My Commission Expires:
December 3, 1968.