

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 27 Twp. 19 Rge. 7 (#) (W)

Location as "NE/CNW/SW" or footage from lines. NE NW SW

Lease Owner Woodman & Tannitti

Lease Name Cain Well No. 1

Office Address Box 387 Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-9-56 19

Application for plugging filed 6-9-56 19

Application for plugging approved 6-9-56 19

Plugging commenced 6-9-56 19

Plugging completed 6-9-56 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rule Durkee

Producing formation Arb. Depth to top 3626 Bottom 3652 Total Depth of Well 3652 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mixed heavy mud and circulated. Set a bridge plug at 224'210', 15 sacks of cement.
Set another plug at 25', 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Tannitti Drilling Co.

Address Box 387 Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
K. T. Woodman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman

SUBSCRIBED AND SWORN TO before me this 13th day of June 1956

My commission expires February 22, 1950

(Address)
Jayne Skinner
Notary Public.

PLUGGING
FILE SEC 27 T 19 R 1W
BOOK PAGE 71 LINE 4

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1956
6-14-1956
CONSERVATION DIVISION
Wichita, Kansas

DRILLING LOG

Company: Brown & Fortier-Woodman & Iannitti Drilling Co.
921 Union Natl. Bank Bldg. - Wichita, Kansas

Lease: Cain
Well: #1 - NE NW SW 27-19-7W, Rice County, Kansas

Contractor: Woodman & Iannitti Drilling Co.
921 Union Natl. Bank Bldg. Wichita, Kansas

Date Comm: 5-29-56
Date Compl: 6-9-56

T. D. 3652 Feet

Casing: 211' 8 5/8"

Figures Indicate Bottom of Formation

0-139	Surface Soil & Sand	2445-2475	Shale & Lime
162	Shale & Sand	2500	Lime & Shale
211	Shale & Red Bed	2570	Lime
236	Shale & Red Bed	2650	Lime
253	Shale & Shells	2718	Lime
305	Shale & Red Bed	2860	Shale & Broken Lime
525	Shale & Red Bed	2878	Shale & Broken Lime
805	Shale & Shells	2938	Lime
1050	Salt & Shale	3035	Lime
1120	Shale & Shells	3084	Lime
1170	Lime & Shale	3121	Lime
1275	Lime & Shale	3180	Lime
1420	Shale & Lime	3205	Lime
1475	Broken Lime	3209	Lime & Shale
1525	Broken Lime	3232	Lime
1580	Shale & Lime	3273	Conglomerate
1685	Shale & Lime	3278	Kinderhook
1800	Shale & Lime	3315	Kinderhook
1885	Broken & Shale	3395	Kinderhook-Shale
1900	Lime & Shale	3479	Kinderhook
2100	Shale & Shells	3496	Mizener
2120	Lime & Shale	3523	Lime
2200	Shale & Shells	3566	Shale & Lime
2355	Shale & Shells	3580	Simpson
2445	Shale & Shells	3626	Simpson Sand & Shale
		3652	Arbuckle
		3652	T. D.

I certify the above to be a true and correct copy of the Driller's Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING CO.

By: K. T. Woodman
K. T. Woodman

PLUGGING	
FILE SEC.	27 T 19 R 7W
BOOK PAGE	71 LINE 4