


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rice County, Sec. 16 Twp. 19S Rge. 7W (X) (W)

Location as "NE/CNW%SW%" or footage from lines SE SE NW

Lease Owner Joe B. Nathan

Lease Name Pulliam Well No. 1

Office Address 604 Brown Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 26, 19 59

Application for plugging filed January 26, 19 59

Application for plugging approved January 26, 19 59

Plugging commenced January 26, 19 59

Plugging completed January 26, 19 59

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3638 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 210 feet. Pushed bottom plug to 210 feet with 6 joints of drill pipe. Set bottom plug with 20 sacks cement through drill pipe. Filled with heavy mud to 40 feet. Set top plug with hulls and 10 sacks cement. Used 3 sacks cement to plug rat hole and put cap on surface pipe.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 28 1959  
CONSERVATION DIVISION  
Wichita, Kansas  
1-28-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Cherry Drilling Co., Inc.  
Address 102 Insurance Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Betty Brandt

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt, Secretary  
102 Insurance Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 59

My commission expires September 5, 1960  
Donna C. Sisk Notary Public

PLUGGING  
FILE SEC. 16 T. 19 R. 7W  
BOOK PAGE 13 LINE 5

CHERRY DRILLING CO., INC.  
102 INSURANCE BUILDING  
WICHITA 2, KANSAS

ROTARY DRILLING LOG

Lease:	Pulliam	Company:	Cherry Drilling Co., Inc. et al 102 Insurance Building Wichita 2, Kansas
Well No.:	1		
Location:	SE SE NW Section 16-19S-7W Rice County, Kansas	Contractor:	Cherry Drilling Co., Inc.
Elevation:	1757 D. F. 1755 Gr.	Geologist:	Charles S. Brown 202 Rule Building Wichita, Kansas
Well Commenced:	1-14-59	Surface Pipe:	11 Jts. used 8-5/8", 28#, 222.32 overall less threads cemented with 135 sacks common cement, 2% CC
Well Completed:	1-26-59		

Casing: D & A

\*\*\*\*\*

0 - 220	Red bed & shale	2750 - 2810	Lime & shale
220 - 475	Red bed, shale & shells	2810 - 2900	Shale & sand
475 - 1115	Shale & shells	2900 - 3175	Lime
1115 - 1220	Lime & shale	3175 - 3230	Lime & shale
1220 - 1530	Lime	3230 - 3250	Shale
1530 - 1775	Shale & lime	3250 - 3310	Lime & shale
1775 - 1885	Shale	3310 - 3520	Shale
1885 - 1970	Shale & lime	3520 - 3555	Lime
1970 - 2205	Shale	3555 - 3608	Shale & Lime
2205 - 2470	Shale & Lime	3608 - 3638	Arbuckle
2470 - 2595	Lime & Shale	3638	R. T. D.
2595 - 2750	Lime		

The above is true and correct to the best of my knowledge.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 28 1959

*Arthur J. Brandt*  
Secretary

Subscribed and sworn to before me this 27th day of January, 1959.

*Donna C. Sisk*  
Donna C. Sisk Notary Public

My Commission Expires: September 5, 1960.

PLUGGING  
FILE SEC. 16 T. 19 R. 7W  
BOOK PAGE 13 LINE 5