

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rice SEC. 14 TWP. 19 RGE. 6 E/W  
Location as in quarters or footage from lines:  
SE SE SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner F. G. Holl  
Lease Name Barta Well No. 1-14  
Office Address 6427 East Kellogg, Wichita, Ks 67207  
Character of Well (Completed as Oil, Gas or Dry Hole): dry hole  
Date Well Completed August 12, 1983  
Application for plugging filed July 15, 1983  
Plugging commenced 7:00 PM August, 12, 1983  
Plugging completed 8:45 PM August 12, 1983  
Reason for abandonment of well or producing formation dry hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merlin Unruh  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3360  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	207.92	none

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud through open ended drill pipe  
50 sacks at 270'; 1/2 sack Hulls, plug and 10 sacks at 40';  
10 sacks in rathole with joint of drill pipe. Used 50-50  
Pozmix + 2% Gel. By Howco.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Co., PO Box 129, Sterling, Ks.

STATE OF Kansas COUNTY OF Rice, ss.  
Harry J. Mead (~~employee of owner~~) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Harry J. Mead  
Harry J. Mead, V.P.  
(Address)  
PO Box 129, Sterling, Ks 6757

SUBSCRIBED AND SWORN TO before me this 15 day of August, 1983



[Signature]  
Notary Public.

My Commission expires: AUG 18 1983

WICHITA, KANSAS

4-18-1983

WELL LOG - - - - - BARTA 1-14

located SE SE SW, Section 14-19s-16w, Rice  
County, Kansas

OWNER - F. G. Holl  
ROTARY DRILLING CONTRACTOR - Sterling Drilling Company

COMMENCED - August 8, 1983  
COMPLETED - August 12, 1983  
TOTAL DEPTH - 3360'

LOG

0 - 225	Surface soil, red bed
225 - 561	Red bed & shale
561 - 1440	Shale & lime
1440 - 3360	Shale & lime

CASING RECORD

Ran 5 joints 8 5/8" 24# casing.  
207.92' set at 220' KB. Cemented  
with 160 sacks Common + 3% cc.  
By Howco. Plug down at 11:45 AM  
8-8-83

Plugged

DEVIATION SURVEY

1° at 3290'

0808 11:45  
**AUG 1 R 1983**

WILLIAMS, KANSAS