

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-159-21,508 00 00

LEASE NAME Nelson

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 14 TWP. 19 RGE. 6W ~~XE~~ or (W)

COUNTY Rice

Date Well Completed

Plugging Commenced 7-1-91

Plugging Completed 7-3-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS P.O. Box 158 Belpre, Ks. 67519

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3448'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION
 7-15-1991

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out	DATE
				8 5/8"	222'	none	III 15 1991
				4 1/2"	3443'	2315'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Sanded bottom to 3330' ran 4 sacks cement. Shot pipe @2500', 2315'
 Spotted 35 sacks @950' pulled up to 350' circulated to surface.
 120 sacks 65/35 4% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 12 day of July, 19 91

Irene Herzberg
 Notary Public

My Commission Expires:



15-159.21508.00.00

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

RECEIVED
STATE COMMISSION
APR 23 1991
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG ----- NELSON #3-14
Located: SE SW NE, Section 14-19S-6W, Rice County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 15, 1982
COMPLETED: October 20, 1982

TOTAL DEPTH: 3450'

LOG

CASING RECORD

0 - 224 Shale	Ran 5 joints new 8 5/8", 24# casing. Cemented with 165 sacks Common with 3% cc. Plug down at 6:15 PM, 10-15-82, by Howco.
224 - 654 Red Bed and Shale	
654 - 3450 Shale and Lime	Ran 8 joints 4 1/2", 10.5# used casing and 77 joints 4 1/2", 10.5# new casing. 3433.67' set at 3443' K.B. Cemented with 100 sacks Lite and 125 sacks 50/50 Pozmix, plus our regular additives. Plug down at 10:45 AM, 10-20-82, by Howco. Plugged rathole with 10 sacks Lite.

Deviation Survey: 1 1/2° at 3450'