


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 27 Twp. 19S Rge. 8 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE/4 SE/4 NW/4
Lease Owner Dozier Oil Company,
Lease Name Stewart Well No. 1
Office Address Union National Bank Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-1-52 19
Application for plugging filed 12-1-52 19
Application for plugging approved 12-1-52 19
Plugging commenced 12-1-52 19
Plugging completed 12-1-52 19
Reason for abandonment of well or producing formation
Dry Hole.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3336 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	218	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 215 feet to 35 feet for each plug set.

USED TWO Halliburton plugs. Pushed one plug to the depth of 215 Feet cemented with 15-sacks cement through drill pipe. Pushed top plug to the depth of 35-Feet cemented with 5-sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1952
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Stag Drilling Inc.,
Address Box 169, Chase, Kansas.

STATE OF Kansas COUNTY OF Rice, ss.
C.L. Tyrrell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.L. Tyrrell
(Address) Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 2 day of Dec, 1952

Orlando Miller
Notary Public.

My commission expires 3/1/55

PLUGGING
FILE DEC 27 1952
BOOK PAGE 63 PAGE 14

CONTRACTOR'S WELL LOG

OPERATOR Dozier Oil Co Farm Name Stewart Well No. 1

Location SE/4 SE/4 NW/4 Sec. 27-19S-8W COUNTY Rice STATE Kansas

COMMENCEMENT DATE 11/18/52 COMPLETION DATE 12/1/52

LOG OF WELL

All measurements from top of rotary bushing

From	To	Formation	Deviation From Vertical	Remarks
0	218	Surface hole		
218	830	Red Red shale shells		
830	1080	Salt		
1080	1350	Shale lime shells	0° -1160'	
1350	1460	Lime sand		
1460	1905	Lime shale		
1905	2180	Shale shells		
2180	2300	Lime		
2300	2345	Sandy shale		
2345	2435	Lime shale		
2435	2765	Lime		
2765	2769	Shale		
2769	2859	Lime shale		
2859	3210	Lime		
3210	3225	Lime shale		
3225	3240	Congl.		
3240	3336	Shale		Total Depth Dry hole

Set 218' (11 jts) 8 5/8" casing

STATE OF KANSAS)
 SS
COUNTY OF RICE)

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

STAG DRILLING INC.

BY: C. L. Ourrell
President

Subscribed and sworn to before me this 2nd Day of December, 1952

My Commission Expires 3/1/55

Orlando Miller
Notary Public

RECEIVED
NOTARY COMMISSION
- 5 1952
NOTARY DIVISION
NOTARY KANSAS

PLUGGING
FILE SEC 27-19-S-8W
BOOK PAGE 63 LINE 14