


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 18 Twp. 19 Rge. 8 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C of SW SE



Locate well correctly on above Section Plat

Lease Owner Glickman Oil Company
Lease Name Reed Well No. 1
Office Address 702 S. St. Francis, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 5-26-66 19
Application for plugging filed 5-26-66 19
Application for plugging approved 5-26-66 19
Plugging commenced 5-26-66 19
Plugging completed 5-26-66 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott & Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3424' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	212'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Mud to 210' 1/4 sx Hulls, Plug and 20 sxs cement through drill pipe, mud to 40' with plug and 1/2 sxs Hulls 10 sxs cement to surface.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 3 1966

CONSERVATION DIVISION
Wichita, Kansas
6-3-1966

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glickman Oil Company
Address Box 11104, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Milton Glickman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Milton Glickman
Box 11104, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 66

My commission expires 11-19-67
Lorella Schauf
Lorella Schauf Notary Public.

GLICKMAN OIL COMPANY
P.O. Box 3104
Wichita, Kansas 67211

DRILLERS WELL LOG

Company: Glickman Oil Company	Location: C of SW SE
Farm: Reed	18-19S-8W
Well No. 1	Rice County, Kansas
Commenced: 5-17-66	Elevation: 1708' KB
Completed: 5-25-66	Geologist: Robert Gill
Total Depth: 3424'	Production: D&A
Casing: 8-5/8" @ 212' w/175 sxs	

Figures Indicate Bottom of Formations.

		<u>TOPS</u>	
212'	Shale & Shells	Anhydrite	329'
303'	Red Bed	Heebner	2716' -1008'
329'	Anhydrite	Brown Lime	2849' -1141'
835'	Shale & Red Bed	Lansing	2880' -1172'
1175'	Shale	Kansas City Base	3285' -1588'
1320'	Shale & Lime	Arbuckle	3396' -1688'
1405'	Lime Shale		
1480'	Sandy Lime		
1520'	Lime & Shale		
1755'	Lime with Shale Streaks		
2020'	Lime & Shale		
2186'	Shale & Lime		
2490'	Lime & Shale		
2645'	Lime		
2850'	Lime & Shale		
3035'	Lime		
3105'	Lime (Cherty)		
3210'	Lime		
3285'	Shale with Lime		
3298'	Lime & Shale		
3375'	Lime		
3405'	Shale - PT		
3424'	Arbuckle		
3424'	Total Depth		


RECEIVED
STATE CORPORATION COMMISSION
JUN -3 1966
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Reed #1


Milton Glickman

Subscribed and sworn to before me this 31st day of May, 1966.


Lorella Schauf
Notary Public

My Commission Expires: Nov. 19, 1967