


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or E-Mailer Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



Locate well correctly on above Section Plat

Rice County, Sec. 15 Twp. 19S Rge. (E) 8 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Glickman Oil Company
Lease Name Thiessen Well No. 1
Office Address 702 South St. Francis, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 4 1961
Application for plugging filed August 4 1961
Application for plugging approved August 4 1961
Plugging commenced August 4 1961
Plugging completed August 4 1961
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation Depth to top Bottom Total Depth of Well 3270 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1961	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Plug @ 210' w/20 sxs.
Plug - 8 sxs. cement @ 35'
2 sxs. in Rat hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1961
CONSERVATION DIVISION
Wichita, Kansas
8-22-1961

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glickman Oil Company
Address P. O. Box 3104 - Washington St. Station, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Milton Glickman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Milton Glickman*
Box 3104, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 1961

My commission expires November 19, 1963
Lorella Schauf
Lorella Schauf Notary Public.

GLICKMAN OIL COMPANY

P. O. Box 3108
Wichita, Kansas

DRILLERS WELL LOG

Company: Glickman Oil Company

Location: SW SW NE

Farm: Thiessen Well No. 1

Sec. 15-19S-8W
Rice County, Kansas

Commenced: July 27, 1961
Completed: August 4, 1961
Total Depth: 3270'

Elevation: 1754 RB

Casing: 8-5/8" @ 196' w/125 sxs.

Production: D&A

Figures Indicate Bottom of Formations.

35	Surface Shale		
48	Sand		
196	Shale w/shells		
208	Shale		
520	Red Bed		
840	Shale & Shells		
1050	Shale & Salt		
1505	Shale & Lime		
1640	Lime		
2050	Lime & Shale		
2280	Shale & Lime		
2300	Shale & Sand		
2742	Lime		
2772	Sand		
2780	Sand & Shale		
2863	Shale & Lime		
3177	Lime		
3189	Cong. (Cherty)		
3225	Cong.		
3241	Lime Shale		
3253	Arbuckle Lime		
3270	Lime		
3270	RTD		

		<u>TOPS</u>	
		Heebner	2692
		Toronto	2719
		Douglas	2732
		Brown Lime	2820
		Lansing	2854
		Conglomerate	3176
		Arbuckle	3241

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1961
CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Thiessen #1

Milton Glickman
Milton Glickman

Subscribed and sworn to before me this Ninth day of August, 1961

Lorella Schauf
Lorella Schauf Notary Public

My Commission Expires: November 19, 1963