

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR J D Production Co.

ADDRESS PO Box 309

PHONES (316) 824-6156 OPERATORS LICENSE NO. 8917

Character of Well Good

Date Well Completed 10-13-75

Plugging Commenced 12-27-99

(Oil, (G) Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-28-99

The plugging proposal was approved on _____ (date)
by _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation Kridel sand Depth to Top 1228 Bottom 1250 T.D. 1290'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Kridel sand</u>	<u>Surface pipe</u>	<u>TOP</u>	<u>205'</u>	<u>7"</u>	<u>OCT 1975</u>	
	<u>Casing</u>	<u>TOP</u>	<u>1290'</u>	<u>4"</u>		<u>685' 5-28-99</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Sanded up to 1160' & plugged Bottom Hole with 5 sacks cement to 1060' cut pipe off at 765' pulled to 685' pumped in 30 sacks cement, pulled pipe to 260' pumped in 30 sacks of cement and six to top.

Name of Plugging Contractor J D Production Co. License No. 8917

Address PO Box 309 Geneseo, KS 67444

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dean Gustus JUN 21 1999

STATE OF Kansas COUNTY OF Rice, ss. 6-21-1999

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Gustus

(Address) PO Box 309 Geneseo, KS 67444

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 99

STEVEN K. PRICKETT
Notary Public

My Commission Expires: 8/29/02

