

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Kiowa County, Sec. 32 Twp. 30S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines C NW SW  
Lease Owner Rosen Oil Corporation  
Lease Name Wesley Medical Center Well No. 1  
Office Address 200 Sutton Place, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 16, 19 70  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 16, 19 70  
Plugging completed November 16, 19 70  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein of Attica  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5160 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	540'	8-5/8"	540'	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth yo 520 Feet;  
Plug and 150 sax Cement; Mud to 300 Feet,  
Plug and 30 sax Cement; Mud to 40 Feet,  
1/2 sax Halls, Plug bridged w/Kelly and  
10 sax Cement to Base of Cellar; 2 sax  
Cement in Rat Hole. Job Completed at  
10:30 A.M. 11/16/70 by Sun Oil Well  
Cementing Co.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 18 1970  
CONSERVATION DIVISION  
Wichita, Kansas

11-18-1970

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sun Oil Well Cementing Co.  
Address Box 169, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
T. M. McCaul, Jr. of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. M. McCaul Jr.  
500 Bitting Building, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 17th day of November, 19 70

Louise K. Whitted  
Louise K. Whitted - Notary Public.



My commission expires November 26, 1970.

DRILLERS LOG

WESLEY MEDICAL CENTER NO. 1

CASING RECORD:	OPERATOR: Rosen Oil Corporation	DESCRIPTION:
8-5/8" @ 540' w/350 sax cement	CONTRACTOR: Sage Drilling Co.	C NW SW Sec. 32-30S-18W Kiowa County, Kansas
TOTAL DEPTH: 5160'	COMMENCED: November 1, 1970	ELEVATION: 2183KB
	COMPLETED: November 16, 1970	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock, Shale & Red Bed	0	50	
Shale, Shells & Red Bed	50	435	
Red Bed & Shale	435	690	
Shale	690	1011	
Shale & Shells	1011	2421	
Lime & Shale	2421	2535	
Shale & Lime	2535	2660	
Lime & Shale	2660	2965	
Lime	2965	3115	
Lime & Shale	3115	3460	
Lime	3460	3640	
Lime & Shale	3640	4220	
Shale & Lime	4220	4310	
Lime	4310	5160	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 18 1970  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By *[Signature]*



Subscribed and sworn to before me this 17th day of November, 1970.

*[Signature]*  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.