

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kiowa County. Sec. 32 Twp. 30S Rge. (E) 18 (W)

Location as "NE/CNW/SW" or footage from lines C SW SE SE  
Lease Owner Sunray Mid-Continent Oil Company  
Lease Name Barngrover Well No. 1  
Office Address Box 788, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 10 19 58  
Application for plugging filed March 10 19 58  
Application for plugging approved March 12 19 58  
Plugging commenced March 10 19 58  
Plugging completed March 10 19 58  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp  
Producing formation Depth to top Bottom Total Depth of Well 5140 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	514	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 240', 1/2 sack hulls and 35 sacks cement. Mud to 40', 1/2 sack hulls and 15 sacks cement, cement to surface. Plugging completed.

Log attached.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1958 3-17-58

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
N. E. Montgomery (employee of owner) or (owner/proprietor) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery  
Box 788, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 58

[Signature]

My commission expires December 24, 1960

Notary Public.

PLUGGING  
SEC. 32 T. 30 R. 18 W  
BOOK PAGE 88 LINE 27

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
March 11, 1958

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: February 20, 1958  
Drilling Completed: March 10, 1958

Barngrover #1 SE/4 Sec.  
32-30S-18W, Kiowa County,  
Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation:

Surface	0
Sand & Red Bed	145
Red Bed	517
Shale & Shells	1570
Anhydrite Shells	1620
Shale & Shells	1640
Shale	1950
Shale & Shells	2160
Anhydrite	2200
Shale & Shells	2260
Shale & Lime	2315
Lime & Shale	2525
Lime	2720
Lime & Shale	2810
Lime	2862
Lime & Shale	3060
Shale & Lime	3685
Lime & Shale	4005
Lime	4056
Lime & Shale	4233
Shale & Lime	4285
Lime & Shale	4545
Lime	4625
Lime & Shale	4661
Lime	4733
Lime & Shale	4776
Lime	4828
Lime & Shale	4982
Lime	5140 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Barngrover #1 SE/4 Section 32-30S-18W, Kiowa County, Kansas.

Frank E. Stickle  
Frank E. Stickle

Lillian T. Bondam  
Notary Public  
February 13, 1960  
My Commission Expires

PLUGGING  
FILE SEC. 32-30S-18W  
BOOK PAGE 88 LINE 27