

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rice

Location: SW- SW- NE- Sec. 15 Twp. 19S Rge. 8 EX (W) _____

Name of Field: Wild cat Total Depth: 3270'

I have this date completed supervision of plugging of:

Lease Name: Thiessen Well No. T

Operator's Full Name: Glickman Oil Company.

Complete Address: 702 S. St. Francis, Wichita Kansas.

Plugging Contractor Company Tools

Address: _____ License No. Rotary

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 10:PM Day 4 Month 8 Year 61

The above well was plugged as follows:

After pulling drill pipe filled hole w/ 36 vis mud from T.D. 3270' back to 210', set a

Halco plug 1/2 sak hulls and 20 sax cement. Filled hole w/ 36 vis mud from 130' back to

35' set a Halco plug 1/2 sak hulls and 8 sax cement back to zero.

8-5/8" surface pipe 4' below ground level. Filled rat hole w/ mud and 2 sax cement

3' below ground level.

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1961
CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 8/18/61
INV. NO. 3621-W