

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Barton

Location: SW SW NW Sec. 36 Twp. 20 Rge. 12W (E) (W)

Name of Field: _____ Total Depth: 3459

I have this date completed supervision of plugging of:

Lease Name: Panning "A" Well No. _____

Operator's Full Name: Birmingham-Bartlett Drilling Company

Complete Address: 300 Kaufman Bldg., Wichita 2, Kansas

Plugging Contractor Ralph Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11:00 AM Day 23 Month 3 Year 1962

The above well was plugged as follows:

8 5/8" 239' Gwc.

Sanded hole back to 3380' & dumped 4 sax cement with dump bailer.

Circulated hole with mud. Pulled pipe to 400' & displaced 20 sax cement

thru drill pipe. Pulled pipe to 190', & displaced 20 sax cement thru

pipe with pump truck. Mudded hole to 40', set rock bridge, & 10 sax

cement, cementing to base of cellar.

Signed: Don Truman
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED

DATE 3/30/62

INV. NO. 4736-41

3-29-62
STATE CORPORATION COMMISSION
MAR 27 1962
CONSERVATION DIVISION
Wichita, Kansas