

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building

WICHITA, KANSAS 67202

16 December 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-097-20803

Dear Sir:

Mr. Jack Toy of American Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Maurice L. Brown Co.

Complete Address: Box 11320 Kansas City Mo. 64112

Lease Name: J. C. Hurd Well No. D-3

Location: SE-SW Sec. 36 Twp. 30 Rge. 18W(E) (W)

County: Keowa Total Depth: 5170'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Toy was instructed to plug the well as follows:

There is 511' of 8 3/4" surface casing. Cement is isolated. All fresh water is behind surface casing. 1st plug with hole foot of heavy mud at 1000' with 50 lbs of cement. 2nd plug pushed rubber plug to 490' and pumped 35 lbs of cement on top of it. 3rd plug on solid ledge at 40' to 0' with 10 lbs of cement. Then they pumped 5 lbs of cement rat hole. The cement used was common cement. The farmer wants to keep water well, so they were advised about recording it with K.C.C. The plugging was accomplished by Halliburton.

Very truly yours,

Paul Luther
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1981

CONSERVATION DIVISION
Wichita, Kansas

12-22-1981